



**Abbreviations (where applicable)**

- BT - Telecom cover
- CPS - Paving slabs
- Dc - Drainage channel
- DK - Drop kerb
- DPC - Damp proof course level
- EL - Eaves level
- FL - Floor level
- EP - Electricity pole
- Fh - Fire hydrant
- Fw - Foul water drainage run
- G - Gully
- IC - Inspection cover
- Jb - Junction box
- Lp - Lamp post
- MH - Man hole
- NFI - No further info
- Re - Recess
- RL - Ridge level
- RNP - Road name plate
- Rs - Road sign
- Rwp - Rainwater downpipe
- SC - Security camera
- St - Water stop tap
- Sw - Water stop valve
- Sv - Stay wire
- Sw - Storm water drainage run
- Tp - Telegraph pole
- TOW - Top of wall level
- UTL - Unable to lift (IC)
- WL - Wall light
- WM - Water meter
- RE - Rodding eye

**Survey Control Information**  
 Level Datum - Site bench mark used:  
 Garage floor level 48.05

**Survey notes**  
 This survey has been carried out at an accuracy commensurate with the scale shown on the title block of the drawing. Enlarging the drawing by digital means will not increase the accuracy of the survey.

Taking dimensions from the drawing is not recommended and measurements for design/construction should be taken from the digital version only, although a scale rule can be used for basic layout and check measurements.

Building wall thicknesses, if shown are for illustration purposes only.

**Trees**  
 Whilst every effort has been made to correctly identify species of trees on the site, we advise that an arboriculturalist be consulted before any final decisions are made.

**Tree legend**  
 t - trunk diameter  
 s - spread diameter  
 h - approximate height

Tree canopies have been shown as an average spread unless otherwise drawn.

**Fences**

- BW - Barbed wire
- CB - Closed board
- CL - Chain link
- CP - Chestnut paling
- CW - Chicken wire
- IR - Iron rail
- IW - Interwoven
- LL - Larch lap
- PC - Post & chain
- PR - Post & rail
- PW - Post & wire
- WM - Wire mesh

**Services**  
 While all reasonable care has been taken in locating the underground services shown on this plan the completeness or accuracy of the information cannot be guaranteed.

Users are advised to satisfy themselves before connections are made.

**Coordinate table**

Station	Easting	Northing	Level
STN1	495345.502	158658.658	47.918
STN2	495335.424	158637.437	48.006
STN3	495366.651	158641.733	48.008
STNEV1	495372.185	158647.495	50.327
STNT1	495345.221	158650.519	49.674

**Key**

- PORCELAIN PAVING - Light grey
- RECESSED MANHOLE COVER - Porcelain filled
- GRANITE STONE CHIP - Silver grey
- BED - Areas for bed preparation
- LAWN - Areas to be turfed
- CONCRETE
- METAL EDGING - Position of metal edging
- STEP UP
- TREE TRUNK POSITION - Existing
- TREE TRUNK POSITION - Proposed
- TREE ROOT BALL POSITION - Proposed
- TREE CANOPY - Proposed

PLEASE READ IN CONJUNCTION WITH ALL WORKING DRAWINGS. Setting out to be agreed on site with the project supervisor.

All dimensions to be checked on site by the contractor, any discrepancies to be reported immediately to the project supervisor and consultant.

Do not scale from this drawing.



**NETTLES & PETALS DESIGN**

Nettles & Petals Design  
 Rhoadler, Old Compton Lane,  
 Farnham, Surrey, GU9 8EG

Liz Frost  
 07879 645107  
 07545 017741  
 liz@nettlesandpetalsdesign.co.uk

Darren Lincoln  
 07545 017741  
 darren@nettlesandpetalsdesign.co.uk

CLIENT	XXXXXXXXXX X XXXX XXXXXXX
PROJECT	XXXXXXXX XXXX
LOCATION	XXXXXXXX XXXX, XXXXXXX, XXXXXXX, XXXXXXX, XXXXX XXX
DRAWING TITLE	Soft Landscaping Planting Plan
DATE	Wednesday 26th August 2021
SCALE	1:50 @ A1
DRAWN BY	Darren Lincoln
NUMBER	LS1.05.02
REVISION	R0

These drawings are copyright © 2021

**Plant Key**

	Hebe rakiensis	x 16		Rosa A Whiter Shade of Pale = 'Peafanfare' (HT)	x 5		Verbena bonariensis 'Lollipop' (PM)	x 32
	Pittosporum tenuifolium 'Oliver Twist'	x 17		Rosa King's Macc = 'Frydisco' (HT)	x 6		Verbena bonariensis	x 23
	Pittosporum tenuifolium 'Golf Ball' (PM)	x 31		Rosa 'Julia's Rose' (HT)	x 6		Bulbs	
	Pittosporum tenuifolium 'Tom Thumb'	x 20		Calamagrostis x acutiflora 'Karl Foerster'	x 22		Narcissus 'Thalia' (S)	x 100
	Sarcococca confusa	x 12		Pennisetum alopecuroides 'Little Bunny'	x 15		Allium jesdianum 'Early Emperor'	x 75
	Hydrangea paniculata Little Lime (Jane) (PM)	x 11		Hakonechloa macra	x 62		Allium nigrum	x 60
	Hydrangea arborescens Strong Annabelle = 'Abetwo' (PM)	x 4		Tellima grandiflora	x 73		Camassia leichtlinii 'Alba'	x 30
	Trachelospermum jasminoides	x 3		Anemone x hybrida 'Whirlwind'	x 24			
	Lavandula angustifolia 'Folgate'	x 18		Oenothera lindheimeri 'Whirling Butterflies' (G)	x 23			

**GENERAL NOTES**

This soft landscaping planting plan (LS1.05.02 R0) is not a stand-alone drawing, it is intended to be used in conjunction with all working drawings and alongside the full specification.

For the setting out of the soft landscaping major elements (trees and hedging) please refer to soft landscaping setting out plan (LS1.04.02 R0).

Where any discrepancies occur between drawings, details, general notes and specification, the more stringent requirements shall apply. Details on drawings take precedence over general notes and typical details. Details noted as typical apply to all similar conditions and shall be applied where no specific details are shown.

**BULB PLACEMENT**

Front garden: Narcissus 'Thalia' - Qty 50 to be spread evenly around Tellima grandiflora on either side of front entrance path.

Rear garden: Narcissus 'Thalia' - Qty 50 and Allium jesdianum 'Early Emperor' - Qty 75 to be spread evenly throughout the left and right hand side of the rear sections of the garden (around Hakonechloa macra and Anemone x hybrida 'Whirlwind').

Rear garden: Allium nigrum - Qty 60 to be spread evenly throughout the Pittosporum tenuifolium 'Tom Thumb' side borders, with 30 on either side.

Rear garden: Camassia leichtlinii 'Alba' - Qty 30 to be spread evenly throughout the Pennisetum alopecuroides 'Little Bunny' and Oenothera lindheimeri 'Whirling Butterflies' planted area in front of metal screens.

